

AD-A097 237

KIMBALL (L ROBERT) AND ASSOCIATES EBENSBURG PA
NATIONAL DAM INSPECTION PROGRAM. OHIO RIVER BASIN, CONNEAUTEE C--ETC(U)
MAR 81

F/6 13/13


DACW31-81-C-0012

NL

UNCLASSIFIED

1 of 2
AD-A097 237





MICROCOPY RESOLUTION TEST CHART
 NATIONAL BUREAU OF STANDARDS-1963-A


AD A 097237

OHIO RIVER BASIN
CONNEAUTEE CREEK, ERIE COUNTY

PENNSYLVANIA
EDINBORO LAKE DAM

NDI ID NO. PA-18
DER ID NO. 25-4

BOROUGH OF EDINBORO
PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
FILED
APR

Prepared By
L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG, PENNSYLVANIA
15931

FOR
DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT CORPS OF ENGINEERS
BALTIMORE, MARYLAND
21203

*Original contains color
plates. All DTIC reproductions
will be in black and
white.

MARCH, 1981

DISTRIBUTION
Approved
Dis

⑥ National Dam Inspection Program

OHIO RIVER BASIN,
CONNEAUTE CREEK, ERIE COUNTY.

PENNSYLVANIA

EDINBORO LAKE DAM


(NDI ID NO. PA-18)

DER ID NO. 25-4)

BOROUGH OF EDINBORO.

PHASE I INSPECTION REPORT,
NATIONAL DAM INSPECTION PROGRAM

⑪ Mar 81
12413



DTIC
ELECTE
APR 6 1981
C

Prepared By

L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG, PENNSYLVANIA
15931

15
DACW 31-81-C-0012

FOR

DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT CORPS OF ENGINEERS
BALTIMORE, MARYLAND
21203

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

MARCH, 1981

411007

17

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I REPORT
NATIONAL DAM INSPECTION REPORT

NAME OF DAM	Edinboro Lake Dam
STATE LOCATED	Pennsylvania
COUNTY LOCATED	Erie
STREAM	Conneauttee Creek
DATES OF INSPECTION	October 20, 1980 and January 15, 1981
COORDINATES	Lat: 41° 52.6' Long: 80° 08.2'

ASSESSMENT

The assessment of Edinboro Lake Dam is based upon visual observations made at the time of inspection, review of available records and data, hydraulic and hydrologic computations and past operational performance. The inspection and review of data of the Edinboro Lake Dam did not reveal any problems which require emergency action. The dam appears to be in good condition and adequately maintained.

Edinboro Lake Dam is a high hazard-intermediate size dam. The spillway design flood for a dam of this size and classification is the PMF. The spillway and reservoir are capable of controlling approximately 39% of the PMF. Based on criteria established by the Corps of Engineers, the spillway is termed seriously inadequate due to downstream conditions associated with a failure of the gravity spillway section. Edinboro Lake Dam is classified as an unsafe non-emergency dam.

The following recommendations and remedial measures should be instituted immediately.


1. A more detailed stability analysis of the gravity spillway section should be conducted by a Registered Professional Engineer knowledgeable in dam design and construction in conjunction with a detailed hydrologic and hydraulic analysis of the structure to increase spillway capacity and to assess the stability of the structure. Remedial modifications should be completed as indicated by the analysis.
2. A planned maintenance and operation schedule should be prepared and implemented. The plan should include regular inspections by responsible Borough employees to insure that routine maintenance is conducted at the dam.
3. A warning system should be developed to warn downstream residents of large spillway discharges or imminent failure of the dam.
4. A safety inspection program should be implemented with inspections at regular intervals by qualified personnel.

EDINBORO LAKE DAM
PA 18

5. The facilities to install flashboards in the spillway should be removed.

6. The potential for erosion exists in the area of the grated outlet which provides access to the stop logs in the culvert. Erosion protection should be provided in this area to ensure that erosion does not occur along the toe area and area immediately below the dam.

7. Provision for an upstream shutoff of the concrete conduit should be provided. The culvert should be more thoroughly inspected and modifications made as required.



L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS AND ARCHITECTS

FEB 25, 1981
Date

R. Jeffrey Kimball
R. Jeffrey Kimball, P.E.

APPROVED BY:

27 MAR 1981
Date

James W. Peck
JAMES W. PECK
COL, Corps of Engineers
District Engineer



Overview of Edinboro Lake Dam

TABLE OF CONTENTS

	PAGE
SECTION 1 - PROJECT INFORMATION	1
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	2
SECTION 2 - ENGINEERING DATA	5
2.1 Design	5
2.2 Construction	5
2.3 Operation	5
2.4 Evaluation	5
SECTION 3 - VISUAL INSPECTION	6
3.1 Findings	6
3.2 Evaluation	7
SECTION 4 - OPERATIONAL PROCEDURES	8
4.1 Procedures	8
4.2 Maintenance of Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Warning System in Effect	8
4.5 Evaluation	8
SECTION 5 - HYDRAULICS AND HYDROLOGY	9
5.1 Evaluation of Features	9
5.2 Evaluation Assumptions	10
5.3 Summary of Overtopping analysis	10
5.4 Summary of Dam Breach Analysis	10
SECTION 6 - STRUCTURAL STABILITY	12
6.1 Evaluation of Structural Stability	12
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS/REMEDIAL MEASURES	14
7.1 Dam Assessment	14
7.2 Recommendations/Remedial Measures	14

APPENDICES

- APPENDIX A - CHECKLIST, VISUAL INSPECTION, PHASE I
- APPENDIX B - CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION,
OPERATION, PHASE I
- APPENDIX C - PHOTOGRAPHS
- APPENDIX D - HYDROLOGY AND HYDRAULICS
- APPENDIX E - DRAWINGS
- APPENDIX F - GEOLOGY
- APPENDIX G - STABILITY ANALYSIS

PHASE I
NATIONAL DAM INSPECTION PROGRAM

EDINBORO LAKE DAM
NDI. I.D. NO. PA 18
DER I.D. NO. 25-4

SECTION 1
PROJECT INFORMATION

1.1 General.

a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Edinboro Lake Dam is an earthfill dam with a concrete gravity spillway, approximately 200 feet long and 17.5 feet high. A concrete bridge spans the spillway crest. The length and width of the bridge is 94 feet and 26 feet, respectively. The crest of the earthfill portion of the dam is paved for its entire length. A vertical concrete retaining wall exists along the upstream face of the left abutment embankment section. A vertical retaining wall exists on the downstream side of the left embankment section in the area immediately adjacent to the left abutment of the spillway gravity section. The embankment to the right of the spillway has upstream and downstream slopes equal to 2.0H to 2.5H:1V and are grass covered.

An 7.7 foot wide by 9.5 foot high concrete conduit exists through the earthen embankment with the entrance to the conduit located approximately 40 feet left of the left abutment of the spillway gravity section. The outlet of the conduit consists of a 36" corrugated metal pipe located approximately 70 feet from the downstream toe of the left embankment section.

The spillway is a concrete gravity structure having a length between abutments of 83 feet. There are 6 piers, each 12" wide projecting above the crest. Between the 6 piers there exists iron supports which allow the insertion of flashboards. The 14 individual openings are each approximately 5.5 feet long. Flashboards placed on the crest are supported at one end by the concrete piers and at the other end by the iron posts.

b. Location. The dam is located within the Borough of Edinboro, Erie County, Pennsylvania. Edinboro Lake Dam can be located on the Edinboro North, U.S.G.S. 7.5 minute quadrangle.

c. Size Classification. Edinboro Lake Dam is an intermediate size dam (17.5 feet high, 6627 acre-feet).

d. Hazard Classification. Edinboro Lake Dam is a high hazard dam. Downstream conditions indicate that a loss of more than a few lives is probable should the structure fail. Several dwellings are located approximately 0.2 miles downstream of the dam.

e. Ownership. Edinboro Lake Dam is owned by the Borough of Edinboro. Correspondence should be addressed to:

The Borough of Edinboro
124 Meadville Street
Edinboro, PA 16412
Attention: Mr. Randy Sanders, Borough Manager
814/734-1812

f. Purpose of Dam. Edinboro Lake Dam is used for recreation.

g. Design and Construction History. The Edinboro Lake Dam was reconstructed around 1909 by C.W. Billings, a Contractor from Edinboro. The original wooden structure rotted and failed in February, 1907. Based on a 1918 report located in the PennDER files, there was no damage associated with the failure.

A Grist Mill was built into the left abutment. The foundation wall of the mill was located approximately 7.5 feet from the left abutment of the spillway. The existing concrete conduit was originally the mill race and has a width of 9.5 feet and a depth of 7.7 feet. No information exists as to the date of construction of the mill but it was reported by Mr. Dave Crowe, former Edinboro Borough Manager, that the building was removed in the early 60's. The raceway for the mill was not destroyed and continues to exist through the embankment section as a concrete conduit.

h. Normal Operating Procedures. During the winter months the lake is lowered to the entrance invert of the concrete conduit by removing stoplogs located at its downstream end.

1.3 Pertinent Data.

a. Drainage Area. 16.9 square miles

b. Discharge at Dam Site (cfs).

Maximum known flood at dam site	
(Hurricane Agnes) June, 1972	300
Concrete conduit capacity at normal pool	Unknown
Spillway capacity at top of dam	3255

c. Elevation (U.S.G.S. Datum) (feet). - Field survey based on spillway crest elevation 1197 feet obtained from U.S.G.S. 7.5 minute quadrangle.

Top of dam - low point	1204.5
Maximum pool - design surcharge	Unknown
Normal pool	1197.0
Spillway crest	1197.0
Upstream portal - concrete conduit (approximate)	1189
Downstream portal - concrete conduit, 36" CMP	1186
Normal tailwater	1188.1
Toe of dam (downstream toe of gravity section)	1187

d. Reservoir (feet).

Length of maximum pool (PMF)	1400
Length of normal pool	800

e. Storage (acre-feet).

Normal pool	2475
Top of dam	6627

f. Reservoir Surface (acres).

Top of dam	600
Normal pool	250
Spillway crest	250

g. Dam.

Type	Earthfill with concrete gravity spillway
Length	200 feet
Height	17.5 feet
Top width (Minimum)	26 feet
Side slopes (left embankment section)- upstream	Vertical
- downstream	Vertical
Side slopes (right embankment section) - upstream	2.0H to 2.5H:1V
- downstream	2.0H to 2.5H:1V
Zoning	None
Impervious core	None
Cutoff	None
Grout curtain	None

h. Reservoir Drain.

Type	Concrete conduit/ 36" CMP
Length (estimate)	110 feet
Closure	Removable stoplogs
Access	At toe of downstream retaining wall on left embankment section
Regulating facilities	Removable stoplogs

i. Spillway.

Type	Concrete gravity section
Length	83 feet
Crest elevation	1197
Upstream channel	Lake (unrestricted)
Downstream channel	Natural streambed

SECTION 2 ENGINEERING DATA

2.1 Design. Review of available information in the files of the Commonwealth of Pennsylvania, Department of Environmental Resources revealed that some correspondence, permit information and limited detailed drawings of the gravity section and concrete conduit were available for review. No detailed information on the design and original construction of the dam were available for review. All information available was reviewed for this study. The Borough did not provide any additional information.

2.2 Construction. Edinboro Lake Dam was constructed around 1909. No other information is available on construction of the dam.

2.3 Operation. During the winter months the lake is lowered to the entrance invert of the concrete conduit.

2.4 Evaluation.

a. Availability. No engineering data was available for review for the purposes of this report. The owner of the dam is the Borough of Edinboro. A representative of the Borough, Mr. David Crawe, former Borough Manager, was interviewed in regards to the operation and maintenance of the dam.

b. Adequacy. The Phase I Report is based on the visual inspection and hydrologic and hydraulic analysis. Sufficient information exists to complete a Phase I Report.

SECTION 3
VISUAL INSPECTION

3.1 Findings.

a. General. The onsite inspection of Edinboro Lake Dam was conducted by personnel of L. Robert Kimball and Associates on October 20, 1980 and January 15, 1981. The inspection consisted of:

1. Visual inspection of the retaining structure, abutments and toe.
2. Examination of the spillway facilities, exposed portion of any outlet works and other appurtenant works.
3. Observations affecting the runoff potential of the drainage basin.
4. Evaluation of the downstream area hazard potential.

b. Dam. The dam appears to be in good condition. From a brief survey conducted during the inspection, it was noted that the low spot on the top of dam exists near the left abutment on the left embankment section. The crest of the dam is paved for its entire length. A roadway exists across the crest of the dam. A roadway bridge spans the spillway crest. Two vertical retaining walls exist on the upstream and downstream face of the left embankment section. The right embankment section has upstream and downstream slopes equal to 2H:1V to 2.5H:1V. Both the upstream and downstream slopes of the right embankment section are grass covered. No seepage was observed on the downstream face, slopes or beyond the toe of the embankment sections.

c. Appurtenant Structures. A concrete gravity spillway exists about mid-way across the embankment section. The spillway crest is 83 feet long between the abutments and a concrete bridge spans the spillway crest. Six concrete piers exist along the spillway crest with iron posts equally spaced between the 6 piers. The posts and piers are utilized as supports for wooden flashboards.

A concrete culvert exists through the left embankment section with the entrance to the culvert on the upstream face of the left embankment section. The concrete culvert has a width of 9.5 feet and a depth of 7.7 feet. The downstream end of the culvert is controlled by wooden stoplogs. An iron grate which provides an entrance to the stoplogs exists at the toe of a concrete retaining wall on the downstream face of the left embankment section. The potential exists for flows to discharge from the downstream end of the culvert thus producing a potential for erosion at the toe of the dam. A 36" corrugated metal pipe discharges flows from the concrete culvert into the stream below the dam. The concrete culvert can be utilized to drain the reservoir.

d. Reservoir Area. The reservoir slopes are gentle to moderate and do not appear to be susceptible to massive landslides which would affect the storage volume of the reservoir or cause overtopping of the dam by displacing water.

e. Downstream Channel. The downstream channel of the Edinboro Lake Dam is relatively wide for a distance of approximately 5 miles at which point flows in the Conneauttee Creek discharge into the Drakes Mills Dam. The Drakes Mills Dam is located approximately 4 1/2 miles below Edinboro Lake Dam.

3.2 Evaluation. The embankment sections of the Edinboro Lake Dam appeared to be in good condition. The crest of the embankment section consists of a paved roadway. The left embankment section is confined between vertical retaining walls which exist on the upstream and downstream face of the embankment section. No seepage was observed during the inspection.

The concrete gravity section appeared to be in fair condition. No visible deficiencies were observed during the inspections. Flows over the spillway section during the October 20, 1980 inspection and heavy snow which covered the spillway section during the January 15, 1981 inspection hampered attempts to observe the downstream face and crest of the spillway section. The roadway bridge which spans the spillway crest is a relatively new structure and appeared to be in good condition.

Inspection of the concrete culvert through the left embankment section was impossible during the October 20, 1980 inspection. During the January 15, 1981 inspection, the waterlevel in the reservoir had been drawn down and a better view to the entrance to the culvert was possible. The visible portion of the entrance to the culvert was unrestricted. A crack was observed on the left interior wall of the culvert. The crack did not appear to be excessive. No determination could be made relative to the actual condition of the culvert. Since the reservoir was lowered, a better view of the upstream face of the retaining wall was possible. The concrete appeared to be in fair condition and no large visible cracks were observed.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedures. The waterlevel in the Edinboro Lake Dam is maintained at the spillway crest elevation, 1197.0. It was reported by the former Edinboro, Borough Manager, Mr. David Crowe that the reservoir level is drawn down during the winter months. During the January 15, 1981 inspection it was observed that the lake was lowered. The possibility of placing flashboards in the spillway exists. However the Borough normally does not install the flashboards.

4.2 Maintenance of the Dam. No planned maintenance schedule exists for the Edinboro Lake Dam. Maintenance on the dam is conducted on an unscheduled, as-needed basis.

4.3 Maintenance of Operating Facilities. The concrete culvert which exists through the left embankment section is equipped with stoplogs on the downstream end of the culvert. It was reported by Mr. David Crowe, that the reservoir is lowered during the winter months. It was observed during the January 15, 1981 inspection that the lake was in a drawn down condition. The culvert is capable of reducing the water level in the reservoir.

4.4 Warning System in Effect. There is no warning system in effect to warn downstream residents of large spillway discharges or imminent failure of the dam.

4.5 Evaluation. The condition of the Edinboro Lake Dam is considered good. There was no warning system in effect to warn downstream residents at the time of the inspection. An emergency action plan should be available for every dam in the high and significant hazard category. Such plans should outline actions to be taken by the operator to minimize downstream effects of an emergency and should include an effective warning system. An emergency action plan has not been developed, the owner should develop such an action plan.

Since the dam was in a near drained condition as observed during the January 15, 1981 inspection, it is evident that the stop logs in the concrete culvert were removed. A close visual inspection of the stop log retaining structure at the downstream end of the concrete culvert was not possible during the January 15, 1981 inspection due to heavy snow.

SECTION 5 HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features.

a. Design Data. The DER files did not contain any hydrologic or hydraulic design calculations used in the design of these facilities. No calculations or design data pertaining to hydrology or hydraulics were available.

b. Experience Data. No rainfall, runoff or reservoir level data were available. The information contained in the DER correspondence file indicated that an old dam existed at the site which rotted and failed about February, 1907. No damages were associated with the failure of the dam. The present dam was built in 1909 by an Edinboro contractor.

c. Visual Observations. The spillway appeared to be in fair condition. The concrete piers and iron posts which are located along the spillway crest appeared to be in fair condition. Only one flash-board near the right edge of the spillway was in place. No other flashboards existed along the spillway crest.

Discharges through the concrete culvert, which exists through the left embankment section, is controlled by stop logs on the downstream end of the culvert. Flows through the culvert discharge through a 36" corrugated metal pipe. Flow through the culvert would be controlled by the discharge potential of the corrugated metal pipe. The discharge potential was considered to be minimal and therefore, was not considered in the overtopping analysis.

The low point on the top of dam exists near the left abutment. The low spot elevation is not easily identifiable by the naked eye. The low point on the top of dam was selected based on a brief survey conducted during the October 20, 1980 inspection.

d. Overtopping Potential. Overtopping potential was investigated through the development of the probable maximum flood (PMF) for the watershed and the subsequent routing of the PMF and fractions of the PMF through the reservoir and spillway.

The Corps of Engineers, Baltimore District, has directed that the HEC-1 Dam Safety Version systemized computer program be utilized. The program was prepared by the Hydrologic Engineering Center (HEC), U.S. Army Corps of Engineers, Davis, California, July, 1978. The major methodologies or key input data for this program are discussed briefly in Appendix D.

5.2 Evaluation Assumptions. To enable the completion of the hydraulic and hydrologic analysis for this structure, it was necessary to make the following assumptions.

1. Pool elevation prior to the storm was at the spillway crest elevation, 1197.0.
2. The top of dam was considered the low spot elevation, 1204.5.
3. The flashboard retaining structure which exists on the spillway crest contains 6 concrete piers approximately 1 foot wide. These 6 concrete piers reduce the weir length by 6 feet. This condition was not considered in the analysis since the concrete culvert would discharge a flow which was considered equal to that flow retarded by the 6 concrete piers. No discharge potential was considered for the concrete culvert.

4. The entire spillway crest was assumed to be at elevation 1197.0.

5.3 Summary of Overtopping Analysis. Complete summary sheets for the computer output are presented in Appendix D.

Peak inflow (PMF)	24470 cfs
Spillway capacity	3255 cfs

a. **Spillway Adequacy Rating.** The Spillway Design Flood (SDF) for a dam of this size and classification is the PMF. Based on the following definition provided by the Corps of Engineers, the spillway is rated as seriously inadequate as a result of our hydrologic analysis. Edinboro Lake Dam is classified as an unsafe non-emergency dam.

Seriously inadequate - High hazard classification dams which do not pass 50% of the spillway design flood and where there is a significant increase in the hazard potential for loss of life due to a dam failure.

The spillway and reservoir are capable of controlling approximately 39% of the PMF without overtopping the embankment.

5.4 Summary of Dam Breach Analysis. As the subject dam cannot satisfactorily pass 50% of the PMF (based on our analysis) it was necessary to perform a dam breach analysis and downstream routing of the flood wave. This analysis determines the degree of increase flooding due to dam failure.

Two potential failure conditions were considered during the dam breach analysis. The first breach analysis considered a failure of the embankment at the right abutment due to overtopping. An elevation of 1206 which represents an overtopping in the area equal to 0.20 feet for a duration of less than 2 hours. The second breach analysis considered a failure of the gravity spillway section. An elevation of 1206 was considered as sufficient to cause a failure of the gravity

section. Stability analysis calculations which appear in Appendix G indicate that the potential for failure of the gravity section could occur at an elevation less than 1206. Elevation 1206 was considered since it approximated the maximum reservoir water surface elevation during a 1/2 PMF event. This elevation was also used in calculations of the stability analysis which ultimately indicated that the structure was unstable at this pool elevation.

The flood wave was routed downstream with and without failure considerations. The downstream potential for loss of life and property damage is significantly increased by dam failure as indicated by the analysis. The potential for increased flooding downstream is significant based on the calculated instability of the structure and the potential flood wave associated with such a failure. Therefore, the spillway is rated as seriously inadequate. The dam is classified as an unsafe non-emergency dam.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability.

a. Visual Observations. No erosion was observed on the embankment crest or slopes at the time of inspection. No seepage was observed during the time of inspection. No structural deficiencies were observed that would affect the stability of the embankment section or the concrete gravity spillway.

The embankment crest consists of a paved roadway surface and the left earthen embankment section widens considerably near the left abutment contact.

Flows through the concrete conduit are restricted by the 36" diameter pipe. In past floods, a significant flow through the grating caused erosion of the bank immediately downstream of the dam.

b. Design and Construction Data. Only limited information regarding the design of the concrete gravity section and original grist mill flume were available in the DER files. No construction data was available for review. The concrete spillway gravity section drawing was utilized in the stability analysis calculations located in Appendix G of this report.

c. Operating Records. No operations are conducted at the dam other than the lowering of the reservoir each winter. No records regarding the reservoir levels are maintained at the Borough Office.

d. Post Construction Changes. No post construction changes are known to have occurred since the structure was rebuilt in 1909. A roadway bridge which spans the spillway crest was rebuilt during the early 1960's.

e. Seismic Stability. The dam is located in seismic zone 1. No seismic stability analyses has been performed. Normally, it can be considered that if a dam in this zone is stable under static loading conditions, it can be assumed safe for any expected earthquake loading. Based on the results of the stability analysis contained in Appendix G, a sufficient factor of safety, under static loading conditions may be less than a minimum accepted value. A more detailed stability analysis should be conducted and the analysis should include a determination of seismic stability.

f. Stability Analysis. An approximation of the stability of the gravity spillway section was performed for this study. A check of the stability was performed using the reservoir pool elevation associated with a 1/2 PMF event. A water surface elevation in the reservoir of 1206.0 was considered for our analysis. The assumptions used for the analysis and the calculations appear in Appendix G of this report.

Based on the assumed conditions, the analyses revealed that the dam is unstable at the pool elevation considered. Factors of safety equal to 1.01 (sliding) and 1.08 (overtopping) resulted from the analysis. The results of the stability analysis indicate that the potential for failure exists at an elevation less than 1206.0. More detailed and accurate analyses are required.

SECTION 7
ASSESSMENT AND RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety. The dam appears to be in good condition and adequately maintained. No erosion or seepage were observed during the inspection. No obvious signs of instability were observed on the concrete gravity section. A major portion of the spillway section was unobservable due to flows over the spillway crest. The visual observations, review of available data, hydrologic and hydraulic calculations and past operation performance indicate that the Edinboro Lake Dam is capable of controlling approximately 39% of the PMF without overtopping the embankment. The spillway is classified as seriously inadequate, unsafe non-emergency.

The stability of the gravity spillway is questionable and a more detailed analysis of the structure should be completed.

b. Adequacy of Information. Sufficient information is available to complete a Phase I Report.

c. Urgency. The recommendations suggested below should be implemented immediately.

d. Necessity for Further Investigation. In order to accomplish some of the recommendations/remedial measures outlined below, further investigations will be required.

7.2 Recommendations/Remedial Measures.

1. A more detailed stability analysis of the gravity spillway section should be conducted by a Registered Professional Engineer knowledgeable in dam design and construction in conjunction with a detailed hydrologic and hydraulic analysis of the structure to increase spillway capacity and to assess the stability of the structure. Remedial modifications should be completed as indicated by the analysis.

2. A planned maintenance and operation schedule should be prepared and implemented. The plan should include regular inspections by responsible Borough employees to insure that routine maintenance is conducted at the dam.

3. A warning system should be developed to warn downstream residents of large spillway discharges or imminent failure of the dam.

4. A safety inspection program should be implemented with inspections at regular intervals by qualified personnel.

5. The facilities to install flashboards in the spillway should be removed.

6. The potential for erosion exists in the area of the grated outlet which provides access to the stop logs in the culvert. Erosion protection should be provided in this area to ensure that erosion does not occur along the toe area and area immediately below the dam.

7. Provision for an upstream shutoff of the concrete conduit should be provided. The culvert should be more thoroughly inspected and modifications made as required.

APPENDIX A
CHECKLIST, VISUAL INSPECTION, PHASE I

CHECK LIST
VISUAL INSPECTION
PHASE I

NAME OF DAM Edinboro Lake Dam COUNTY Erie STATE Pennsylvania ID# PA 18
 TYPE OF DAM Earthfill with concrete gravity spillway HAZARD CATEGORY High 40°
 DATE(s) INSPECTION October 20, 1980 WEATHER Cold and rainy 22°
January 15, 1981 WEATHER Cold with snow flurries TEMPERATURE _____
 POOL ELEVATION AT TIME OF INSPECTION 1197 10/20/80 TAILWATER AT TIME OF INSPECTION 1188.1 10/20/80
1197 1/15/81 M.S.L. None 1181.5/81

INSPECTION PERSONNEL:

R. Jeffrey Kimball, P.E. - L. Robert Kimball and Associates

James T. Hockensmith - L. Robert Kimball and Associates

O.T. McConnell - L. Robert Kimball and Associates

O.T. McConnell

RECORDER

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Appears good.	
RIPRAP FAILURES	None.	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
VEGETATION	Crest is paved and slopes are grass covered.	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Appears to be good.	
ANY NOTICEABLE SEEPAGE	None.	
STAFF GAUGE AND RECORDER	None.	
DRAINS	None.	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
ANY NOTICEABLE SEEPAGE	None.	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Appears to be all right.	
DRAINS	None.	
WATER PASSAGES	Appears to be all right.	
FOUNDATION	Unknown.	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Close inspection of the gravity section was prevented due to discharge over crest.	
STRUCTURAL CRACKING	None observed.	
VERTICAL AND HORIZONTAL ALIGNMENT	All right.	
MONOLITH JOINTS	Appear all right.	
CONSTRUCTION JOINTS	Not observed.	
STAFF GAUGE OR RECORDER	None.	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	One crack on left interior wall of concrete conduit. No cracking or excessive spalling of concrete surfaces observed.	A more thorough inspection of the culvert should be made to assess the actual condition.
INTAKE STRUCTURE	Unrestricted.	
OUTLET STRUCTURE	36" corrugated metal pipe.	
OUTLET CHANNEL	Natural stream.	
EMERGENCY GATE	Stoplogs.	

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Modified sharp crest. The weir appeared to be in good condition and well maintained. Retaining structures along the crest allow the placement of flashboards.	
APPROACH CHANNEL	Unrestricted.	
DISCHARGE CHANNEL	Natural stream.	
BRIDGE AND PIERS	Roadway bridge spans spillway crest, no bridge piers.	

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	Not applicable.	
APPROACH CHANNEL	Not applicable.	
DISCHARGE CHANNEL	Not applicable.	
BRIDGE AND PIERS	Not applicable.	
GATES AND OPERATION EQUIPMENT	Not applicable.	

DOWNSTREAM CHANNEL


VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Relatively wide channel for a discharge of approximately 5 miles at which point discharges enter the Drakes Mills Dam.	
SLOPES	Appear to be stable.	
APPROXIMATE NO. OF HOMES AND POPULATION	Approximately two homes - 8 people within 0.2 miles of the dam.	

RESERVOIR


VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Gentle to moderate slopes. Appear to be stable.	
SEDIMENTATION	Unknown.	

INSTRUMENTATION


VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None.	
OBSERVATION WELLS	None.	
WEIRS	None.	
PIEZOMETERS	None.	
OTHER	None.	



EDINBORO LAKE DAM
SCALE: 1" = 50'



SPILLWAY SECTION
(NOT TO SCALE)



PROFILE
LOOKING UPSTREAM
(SCALE: 1"=20')

EDINBORO LAKE DAM

APPENDIX B
CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION, OPERATION, PHASE I

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE I

NAME OF DAM Edinboro Lake Dam
ID# PA 18

ITEM	REMARKS
AS-BUILT DRAWINGS	None.
REGIONAL VICINITY MAP	U.S.G.S. quadrangle.
CONSTRUCTION HISTORY	None.
TYPICAL SECTIONS OF DAM	See Appendix G.
OUTLETS - PLAN - DETAILS - CONSTRAINTS - DISCHARGE RATINGS RAINFALL/RESERVOIR RECORDS	Available in DER files. Available in DER files. None. None. None.

ITEM	REMARKS
DESIGN REPORTS	None.
GEOLOGY REPORTS	None.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None.
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None.
POST-CONSTRUCTION SURVEYS OF DAM	None.
BORROW SOURCES	Unknown.


ITEM	REMARKS
MONITORING SYSTEMS	None.
MODIFICATIONS	None since reconstruction in 1909.
HIGH POOL RECORDS	None.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	DER inspection reports available in DER files.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	DER file contains an inspection report which mentions a failure of an original wooden structure which rotted and failed about February, 1907. The present dam was built in 1909 by C.W. Billings, a Contractor of Edinboro. The inspection report remarks that no damage was associated with the original failure.
MAINTENANCE OPERATION RECORDS	None.

ITEM	REMARKS
SPILLWAY PLAN SECTIONS DETAILS	None.
OPERATING EQUIPMENT PLANS & DETAILS	None.

APPENDIX C
PHOTOGRAPHS



EDINBORO LAKE DAM
PHOTO INDEX



P - INDICATES PHOTO LOCATION

EDINBORO LAKE DAM
PA 18

Sheet 1

Front

- (1) Spillway approach. View towards right abutment (note: bridge).
- (2) Spillway crest (note: flashboard retaining structure). View towards right abutment.
- (3) View of spillway gravity section.
- (4) Spillway (view towards left abutment).


Sheet 1



Back

- (5) View of the upstream face at left abutment (note the partial view of the intake for the concrete conduit).
- (6) View of the 36" diameter CMP and pumphouse.
- (7) Downstream channel.
- (8) Downstream exposure.

TOP OF PAGE

1,5	2,6
3,7	4,8





APPENDIX D
HYDROLOGY AND HYDRAULICS

APPENDIX D
HYDROLOGY AND HYDRAULICS

Methodology. The dam overtopping and breach analyses were accomplished using the systemized computer program HEC-1 (Dam Safety Investigation), September, 1978, prepared by the Hydrologic Engineering Center, U.S. Army Corps of Engineers, Davis, California. A brief description of the methodology used in the analysis is presented below.

1. Precipitation. The Probable Maximum Precipitation (PMP) is derived and determined from regional charts prepared from past rainfall records including "Hydrometeorological Report No. 40" prepared by the U.S. Weather Bureau.

The index rainfall is reduced from 10% to 20% depending on watershed size by utilization of what is termed the HOP Brook adjustment factor. Distribution of the total rainfall is made by the computer program using distribution methods developed by the Corps.

2. Inflow Hydrograph. The hydrologic analysis used in development of the overtopping potential is based on applying a hypothetical storm to a unit hydrograph to obtain the inflow hydrograph for reservoir routing.

The unit hydrograph is developed using the Snyder method. This method requires calculation of several key parameters. The following list gives these parameters their definition and how they were obtained for these analysis.

Parameter	Definition	Where Obtained
Ct	Coefficient representing variations of watershed	From Corps of Engineers*
L	Length of main stream channel miles	From U.S.G.S. 7.5 minute topographic
Lca	Length on main stream to centroid of watershed	From U.S.G.S. 7.5 minute topographic
Cp	Peaking coefficient	From Corps of Engineers*
A	Watershed size	From U.S.G.S. 7.5 minute topographic

*Developed by the Corps of Engineers on a regional basis for Pennsylvania.

3. Routing. Reservoir routing is accomplished by using Modified Plus routing techniques where the flood hydrograph is routed through reservoir storage. Hydraulic capacities of the outlet works, spillways and the crest of the dam are used as outlet controls in the routing.

The hydraulic capacity of the outlet works can either be calculated and input or sufficient dimensions input and the program will calculate an elevation discharge relationship.

Storage in the pool area is defined by an area - elevation relationship from which the computer calculates storage. Surface areas are either planimetered from available mapping or U.S.G.S. 7.5 minute series topographic maps or taken from reasonably accurate design data.

4. Dam Overtopping. Using given percentages of the PMF the computer program will calculate the percentage of the PMF which can be controlled by the reservoir and spillway without the dam overtopping.

5. Dam Breach and Downstream Routing. The computer program is equipped to determine the increase in downstream flooding due to failure of the dam caused by overtopping. This is accomplished by routing both the pre-failure peak flow and the peak flow through the breach (calculated by the computer with given input assumptions) at a given point in time and determining the water depth in the downstream channel. Channel cross-sections taken from U.S.G.S. 7.5 minute topographic maps were used in the downstream flood wave routing. Pre and post failure water depths are calculated at locations where cross-sections are input.

HYDROLOGY AND HYDRAULICS ANALYSIS DATA BASE

NAME OF DAM: Edinboro Lake Dam

PROBABLE MAXIMUM PRECIPITATION (PMP) = 23 inches

STATION	1	2	3	4	5	6
Station Description	A	B	C	D	E	F
Drainage Area (square miles)	2.49	1.3	4.56	0.2	1.17	1.17
Cumulative Drainage Area (square miles)	2.49	3.79	8.35	8.55	9.72	10.89
Adjustment of PMF for Drainage Area (%) (1)						
6 hours			112			
12 hours			133			
24 hours			139			
48 hours			156			
72 hours			174			

Snyder Hydrograph

Parameters

Zone (2)			23			
Cp (3)			1.55			
Ct (3)			5.3			
L (miles) (4)	2.77	2.84	4.81	3.36	2.61	2.61
Lca (miles) (4)	1.36	1.52	2.63	2.23	1.40	1.40
tp = Ct(LxLca) 0.3 hrs.	4.91	5.12	7.09	6.23	4.37	5.28

Spillway Data

Crest Length (ft)	60
Freeboard (ft)	7.5
Discharge Coefficient	3.2
Exponent	2.5

- (1) Hydrometeorological Report 33 (Figure 2), U.S. Weather Bureau, U.S. Army Corps of Engineers, 1956.
- (2) Hydrological zone defined by Corps of Engineers, Baltimore District, for determining Snyder's coefficients (3) (Figure 2).
- (3) Snyder's Coefficients.
- (4) L=Length of longest water course from outlet to basin divide.
Lca=Length of water course from outlet to centroid of the centroid of drainage area.

CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 16.91 sq.mi gentle to moderate slopes
ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 1197 - [2475 ac-ft]
ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 1204.5 - [6627 ac-
ELEVATION MAXIMUM DESIGN POOL: Unknown
ELEVATION TOP DAM: 1204.5 - Low spot

SPILLWAY CREST:

a. Elevation 1197
b. Type Modified sharp crest
c. Width Unknown
d. Length 83 feet between spillway abutment
e. Location Spillover Mid embankment
f. Number and Type of Gates None

OUTLET WORKS:

a. Type Concrete conduit - width = 9.5 feet & a depth of 7.66'
b. Location Through left embankment section
c. Entrance inverts Unknown
d. Exit inverts 1188.1
e. Emergency drawdown facilities Concrete conduit with stoplogs

HYDROMETEOROLOGICAL GAUGES:

a. Type None
b. Location None
c. Records None

MAXIMUM NON-DAMAGING DISCHARGE: Unknown



L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME EDINBORO LAKE DAM

NUMBER PA-18

SHEET NO. 1 OF 5

BY SYM DATE 12/80

LOSS RATE AND BASE FLOW PARAMETERS

AS RECOMMENDED BY THE BALTIMORE DISTRICT
CORPS OF ENGINEERS.

STRTL = 1 INCH

CNSTL = 0.05 IN/HR.

STR TQ = 1.5 cfs/mi²

QRCSN = 0.05 (5% OF PEAK FLOW)

RTIOR = 2

ELEVATION - AREA - CAPACITY RELATIONSHIP

FROM D.E.R. FILE AND U.S.G.S. 7.5-MIN. QUAD.

SPILLWAY CREST ELEV. = 1197'

INITIAL STORAGE = 802 X 10⁶ GALLONS OR 2461 AC.FT.

AREA AT ELEV. 1197 = 0.39 mi² OR 250 AC.

FROM THE CONIC METHOD FOR RESERVOIR VOLUME,
FLOOD PHOTOGRAPH PACKAGE (HEL-1), DAM
SAFETY VERSION (USER'S MANUAL).

$$\begin{aligned} H &= 3V/A \\ &= 3(2461)/250 \\ &= 29.5 \text{ FT.} \end{aligned}$$

ELEVATION WHERE AREA EQUALS ZERO;

$$1197' - 29.7' = 1167.5'$$

AT ELEV. 1200, AREA = 588 AC.

AT ELEV. 1210, AREA = 891 AC.

ELEVATION (FT)	1167.3	1197	1200	1210
AREA (AC)	0	250	588	891




L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PA-18

SHEET NO. 2 OF 5
BY OTM DATE 12/80

DISCHARGE RATING



NOTE: THE EFFECTIVE LENGTH IS LESS THAN 83' BELOW ELEVATION 1198 (APPROX.). FOR THE PURPOSE OF THIS ANALYSIS THE TOTAL WEIR LENGTH WILL BE CONSIDERED AS 83'.

USE 3.3 FOR THE COEFFICIENT OF DISCHARGE FOR A SHARP CRESTED WEIR.


POOL ELEVATIONS BELOW 1201 FEET WILL BE CONSIDERED AS CREATING A STANDARD WEIR DISCHARGE.

$$USE Q = CLH^{3/2}$$

POOL ELEVATIONS ABOVE 1201 FEET WILL BE CONSIDERED AS CREATING ORIFICE FLOW.

$$USE Q = \frac{2}{3} C \sqrt{2g} L (h_2^{3/2} - h_1^{3/2})$$

$$WHERE C = 0.6 \quad L = 83' \quad g = 32.2$$





L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PK-18

SHEET NO. 3 OF 5
BY STM DATE 12/80

DISCHARGE THRU THE FLUME AT THE LEFT
ABUTMENT WAS NOT CONSIDERED.


ELEV. (FT.)	WEIR		ORIFICE			DISCHARGE *(Q) (cfs.)
	h (FT.)	Q (cfs.)	h ₂ (FT.)	h ₁ (FT.)	Q (cfs.)	
1197	0	0				0
1198	1	274				270
1199	2	775				780
1200	3	1423				1420
1201	4	2191				2190
1202			5	1.6	2440	2440
1204			7	3.6	3115	3120
1206			9	5.6	3663	3660
1208			11	7.6	4138	4140
1210			13	9.6	4563	4560

* VALUES ROUNDED TO NEAREST 10 CFS.

OVERTOPPING PARAMETERS

TOP OF DAM (LOW SPOT) = 1204.3'
LENGTH OF DAM (EXCLUDING SPILLWAY) = 110'

FROM U.S.G.S. 7.5-MIN QUID. AND FIELD INSPECTION
NOTES AND OBSERVATIONS.



#L	30	500	950	1400
#Y	1205	1210	1215	1220

USE C = 2.9
(BROAD CREST)




L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PA-18

SHEET NO. 4 OF 5
BY OTM DATE 12/80

PROGRAM
SCHEDULE:





L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PA-18

SHEET NO. 5 OF 5
BY OTM DATE 1/31

BREACH ANALYSIS

PLAN 1: CONSIDER FAILURE OF THE RIGHT EARTHEN
EMBANKMENT SECTION DUE TO 0.20 FEET
OVERTOPPING DURING A $\frac{1}{2}$ PM P EVENT.

1. BRWID = 10'
2. Z = 0.5
3. ELEM = TAILWATER ELEV. (1188)
4. TFAIL = 2 HRS.
5. WSEL = 1197
6. FAILEL = 1206

PLAN 2: CONSIDER A FAILURE OF THE CONCRETE
SPILLWAY GRAVITY SECTION.

1. BRWID = SECTION LENGTH = 83'
2. Z = 0
3. ELEM = 1188.1
4. TFAIL = 10 MIN OR 0.17 HRS
5. WSEL = 1197
6. FAILEL = 1206

PLAN 3: NO FAILURE CONSIDERED.

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 01 APR 80

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF									
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF EDINBORO LAKE DAM									
RATIOS OF PMF ROUTED THROUGH THE RESERVOIR (PA-00018)									
	A1	A2	A3	B	C	D	E	F	G
1									
2									
3									
4									
5									
6									
7									
8									
9									
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									
41									
42									
43									
44									
45									

FLOW HYDROGRAPH PACKAGE (HLC-1)
DATA SAFETY VERSION JULY 1978
LAST MODIFICATION 01 APR 80

RUN DATE= 81/01/22.
TIME= 08.08.57.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF EDINBORO LAKE DAM
RATIOS OF PMF ROUTED THROUGH THE RESERVOIR (PA-00019)

JOH SPECIFICATION
INJ NHR NMTH IDAY IHR IMIN MLTRC IPLT IPRT INSTAN
2HR 0 10 0 0 0 0 0 -4 0
JOPER NWY LROPY TRACE
5 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
MPLAN= 1 NRATIO= 5 LRATIO= 1
RTIOS= .39 .40 .50 .60 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA A

ISTAG	ICOMP	TECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYDG	IUNG	IAHRA	SHAP	TRSDA	TRSPC	RATIO	ISHOW	ISAME	LOCAL
1	1	2.49	0.00	-2.49	1.00	0.000	0	0	0

PRECIP DATA

SPFE	PMS	RE	R12	R24	R48	R72	R96
0.00	23.00	112.00	122.00	136.00	146.00	0.00	0.00

LOSS DATA

CRDT	STKR	DLTK	ATPL	LOSLP	SEKPS	RTOR	STGTL	CNSTL	ALSMR	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	0.0	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 4.91 CH= 0.52 NIA= 0

RELATION DATA

STRTU = -1.50 QRC5N = -.05 RTOR = 2.00

[illegible]

138.	134.	130.	127.	124.	121.	118.	115.	112.	109.	106.
103.	100.	98.	95.	92.	89.	86.	83.	80.	77.	74.
71.	68.	65.	62.	59.	56.	53.	50.	47.	44.	41.
38.	35.	32.	29.	26.	23.	20.	17.	14.	11.	8.

MO. DA HR. MIN PERIOD RAIN EXCS LOSS LND-OF-PERIOD FLOW MO. DA HR. MIN PERIOD MAIN LACS LOSS COMP V

SUM 13.58 31.09 2.49 196267.
 7853.11 790.11 83.11 5557.661

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA W

ISTAU	ICOMP	ILCUP	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTO
2	0	0	0	0	0	0	0	0

HYDROGRAPH DATA

INVOG	IUNG	TANLA	SNAP	TRSDA	TRSPC	RATIO	ISNUM	ISAME	LOCAL
1	1.32	0.00	1.32	1.00	0.000	0	0	0	0

PHILIP DATA

SPFE	PRS	R6	R12	R24	R48	R72	R96
0.00	23.00	112.00	122.00	136.00	146.00	0.00	0.00

LOSS DATA

LRDPT	STKR	DLTKR	RTIOL	LRAIN	STKRS	RTIOL	STIPL	CNSTL	ALSHR	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	0.00	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 5.12 CP= .55 RTA= 0

RECUSSION DATA

STRT AT -1.00 DRCLOS -0.05 RTIOL= 2.00

UNIT HYDROGRAPH	TH	OF-PERIOD	ORDINATES	LACS	5.12	WDRS	CP=	.55	VAL=	.90
1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.
103.	100.	98.	95.	92.	89.	86.	83.	80.	77.	74.
71.	68.	65.	62.	59.	56.	53.	50.	47.	44.	41.
38.	35.	32.	29.	26.	23.	20.	17.	14.	11.	8.

END-OF-PERIOD FLOW															
MO. DA		HR. MIN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO. DA		HR. MIN	PERIOD	RAIN	EXCS	LOSS	COMP Q
42.			41.	40.	39.	38.	37.	36.	35.	34.	33.				
32.			31.	30.	29.	28.	27.	26.	25.	24.	23.				
22.			21.	20.	19.	18.	17.	16.	15.	14.	13.				
12.			11.	10.	9.	8.	7.	6.	5.	4.	3.				
SUM												33.58	31.09	2.49	100620.

(853.11 790.11 63.11 2849.24)

COMBINE HYDROGRAPHS

COMBINE INFLOW (SUBAREA A AND B)

ISTAG	ICOMP	ILCON	ITAPE	JPLT	JPRT	INAME	ISTAGL	IAUTO
3	2	0	0	0	0	1	0	0

HYDROGRAPH ROUTING

MOD PULS ROUTING

ISTAG	ICOMP	ILCON	ITAPE	JPLT	JPRT	INAME	ISTAGL	IAUTO
4	1	0	0	0	0	1	0	0

ROUTING DATA

OLCSS	CLOSS	AVG	TRES	TSAME	TPRT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

NSIPS NSTDI LAG AMSPK X TSK STORA ISPRAT

1	0	0	0.000	0.000	0.000	0.000	0
---	---	---	-------	-------	-------	-------	---

NORMAL DEPTH CHANNEL ROUTING

QNT1	QNT2	QNT3	ELRVT	ELMAX	RLNTH	SFL
0.00	0.050	0.060	1198.0	1220.0	5280.0	0.00380

CROSS SECTION COORDINATES--STA, ELEV, STA, ELEV--LIC

0.00	1220.00	200.00	1210.00	890.00	1200.00	898.00	1198.00	202.00	1198.00
904.00	1200.00	1300.00	1210.00	1850.00	1220.00				

STORAGE	0.70	0.72	2.02	17.26	49.84	100.17	168.26	254.06	357.63
11/14/74	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18
11/24/74	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18

OUTFLOW	0.00	9.62	37.47	227.78	832.86	2045.78	4031.01	6936.55	10899.17
16047.18	22502.25	30757.32	40729.61	52240.34	65330.64	80046.01	96434.51	114545.80	134430.45
156139.56									

STAGE	1198.00	1199.16	1200.32	1201.47	1202.63	1203.79	1204.95	1206.11	1207.26
1198.62	1209.58	1210.74	1211.89	1213.05	1214.21	1215.37	1216.53	1217.68	1218.84
11220.00									

FLOW	0.00	9.62	37.47	227.78	832.86	2045.78	4031.01	6936.55	10899.17
116047.18	22502.25	30757.32	40729.61	52240.34	65330.64	80046.01	96434.51	114545.80	134430.45
156139.56									

MAXIMUM STAGE IS 1206.1

MAXIMUM STAGE IS 1206.1

MAXIMUM STAGE IS 1204.5
 MAXIMUM STAGE IS 1206.6
 MAXIMUM STAGE IS 1205.9

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA C

STAG	ICOMP	TECON	ITAPE	JPLT	JPRI	IRAME	ISTAGE	IAUTO
5	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

HYDG	IUNG	TAKEA	SNAP	TKSDA	TKSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	4.56	0.00	4.56	1.00	0.000	0	0	0

PRECIP DATA

SPEE	PMS	R6	R12	R24	R48	R72	R96
0.00	23.00	112.00	122.00	136.00	146.00	0.00	0.00

LOSS DATA

LRPT	STKR	DLTKR	RTIOL	ERATN	STRS	RTYOR	STRTL	CNSYL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 7.08 CP= .55 NTA= 0

RECESSION DATA

STATUS= -1.50 GRCSN= -.05 RTIOR= 4.00

UNIT HYDROGRAPH END-OF-PERIOD ORDINATES, LAG= 7.15 HOURS, CP= .55 VOL= .79

1.	3.	7.	11.	15.	21.	26.	32.	39.	45.
52.	59.	67.	74.	82.	90.	98.	107.	115.	123.
132.	141.	150.	158.	166.	176.	181.	188.	195.	201.
206.	211.	216.	220.	224.	228.	230.	234.	235.	236.
237.	237.	236.	235.	233.	229.	224.	220.	215.	211.
207.	203.	199.	195.	191.	187.	183.	180.	176.	173.
169.	166.	162.	159.	156.	153.	150.	147.	144.	141.
138.	136.	133.	130.	128.	125.	123.	120.	118.	115.
113.	111.	109.	106.	104.	102.	100.	98.	96.	94.
92.	91.	89.	87.	85.	84.	82.	80.	79.	77.

MO. DA	HR. MIN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW	CONP Q	RTIOL	PERIOD	RATN	EXCS	LOSS	CONP Q
0													

SUM 33.58 31.09 2.49 254756
 (853.11 740.11 63.11 7213.89)

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA D

ISTAD ICOMP IECOM ITAPE JPLT JPRF INHRL ISTAGE IAUIG

INHYDG IUNG TAREA SHAP TRSDA TRSPC RATIO ISNOW ISAMF LOCAL

HYDROGRAPH DATA

SPFL PMS R6 R12 R24 R48 R72 R96

PRECIP DATA

LOSS DATA

UNIT HYDROGRAPH DATA

TP= 6.53 CP= .55 NTA= 0

RECESSION DATA

STRIU= -1.50 GRCSN= -.05 RTIUR= 2.00

UNIT HYDROGRAPH END-OF-PERIOD ORIGINATES LAG= 6.56 HOURS CP= .55 VOL= .82

1.	4.	9.	15.	22.	29.	37.	45.	54.	64.
73.	83.	94.	104.	115.	126.	137.	149.	161.	172.
184.	196.	207.	217.	227.	236.	245.	252.	260.	266.
272.	277.	282.	286.	289.	291.	293.	294.	293.	292.
289.	284.	278.	272.	266.	260.	255.	249.	244.	239.
233.	228.	223.	219.	214.	209.	205.	200.	196.	192.
188.	184.	180.	176.	172.	168.	165.	161.	158.	154.
151.	148.	145.	141.	138.	135.	132.	130.	127.	124.
121.	119.	116.	114.	111.	109.	107.	104.	102.	100.
98.	96.	94.	91.	90.	88.	86.	84.	82.	80.

END-OF-PERIOD FLOW

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP
-------	-------	--------	------	------	------	------	-------	-------	--------	------	------	------	------

SUM 33.50 31.09 2.49 314598.
(855.11 790.11 63.11 9021.69)

COMPUTATION

INFLOW SUBAREA L

ISTAU	ICOMP	ICOR	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAUD
7	0	0	0	0	0	1	0	0

IHYDG	IUHG	TARLA	SINAP	IRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	1.17	0.00	1.17	1.00	0.000	0	0	0

HYDROGRAPH DATA

PRECIP DATA

SPFL	PMS	R6	R12	R24	R48	R72	R96
------	-----	----	-----	-----	-----	-----	-----

UNIT HYDROGRAPH DATA

TP = 4.81 CP = .55 NTA = 0

RELATION DATA

STIRU= -1.50 URCSH= -.05 KFOR= 2.00

UNIT HYDROGRAPH 100 END-OF-PERIOD ORDINATES, LAG= 4.87 HOURS, CP= .55 VOL= .91

1.	2.	4.	7.	10.	13.	17.	21.	25.	29.
33.	38.	42.	47.	52.	56.	61.	65.	69.	73.
76.	79.	81.	84.	85.	87.	88.	88.	89.	88.
87.	85.	82.	80.	77.	75.	73.	71.	69.	67.
65.	63.	61.	59.	58.	56.	54.	53.	51.	50.
48.	47.	46.	44.	43.	42.	41.	39.	38.	37.
36.	34.	33.	33.	32.	31.	30.	29.	28.	28.
27.	26.	25.	25.	24.	23.	23.	22.	21.	21.
20.	20.	19.	18.	18.	17.	17.	16.	16.	15.
15.	15.	14.	14.	13.	13.	13.	12.	12.	12.

END-OF-PERIOD FLOW

MO. DA	HR. MIN	PERIOD	RAIN	EXCS	LOSS	COMP Q	LOSS	EXCS	RAIN	PERIOD	HR. MIN	NO. DA	PERIOD	LOSS	EXCS	COMP Q
SUM																
												33.58	31.09	2.49	97746.	
												(853.)	(790.)	63.)	2676.27	

SUB-ARE A RUNOFF COMPUTATION

INFLOW SURFACE F

ESTAD	COMP	REC	HAPE	JPL	JORT	HAPE	ESTAG	TAUTO
0	0	0	0	0	0	1	0	0

Годуковъ Г. А. 1871.

	TYPE	TAREA	SQAP	TRDA	FSPC	RATIO	ESOP#	ESAME	LOCAL
	1	2.17	0.00	2.17	1.00	0.000	0	0	0

V J W I) 1 2 1

	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2423	2424	2425	2426	2427	2428	2
--	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---

LOSS DATA										
LIQPT	STNKR	DLTKR	RTIOL	ERAIN	STNKS	RTIOR	SMTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	0.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 9.88 CP= 5.55 NIA= 0

STMFU= -1.50 QRC5N= -.05 RTIUR= 2.00

[illegible]

— 24 —

廣東省立第一中學

THE

SECRET

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

COMBINE HYDROGRAPHS

COMBINE INFLOW (SUBAREAS A,B,C,D,E AND F)

TESTAQ	ICONP	TECON	TYADE	JPLY	JPRY	TEARR	ISAGE	TAUTO
0	4	0	0	0	0	1	0	0

本報廣告部

●●●●●●●●●●

● ● ● ● ● ● ● ● ● ●

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

●●●●●●●●●●

HYDROGRAPH ROUTING,

ROUTE THRU EDINBORO LAKE

I	JPLI	ITAPE	JPLT	INAME	ISTAGE	IAUJO
1	1	1	1	1	1	1

POSTLOG DATA			
GROUP	AVG	15AVG	10PT
0005	1000	1500	1000
0006	1000	1500	1000
0007	1000	1500	1000
0008	1000	1500	1000
0009	1000	1500	1000
0010	1000	1500	1000
0011	1000	1500	1000
0012	1000	1500	1000
0013	1000	1500	1000
0014	1000	1500	1000
0015	1000	1500	1000
0016	1000	1500	1000
0017	1000	1500	1000
0018	1000	1500	1000
0019	1000	1500	1000
0020	1000	1500	1000
0021	1000	1500	1000
0022	1000	1500	1000
0023	1000	1500	1000
0024	1000	1500	1000
0025	1000	1500	1000
0026	1000	1500	1000
0027	1000	1500	1000
0028	1000	1500	1000
0029	1000	1500	1000
0030	1000	1500	1000
0031	1000	1500	1000
0032	1000	1500	1000
0033	1000	1500	1000
0034	1000	1500	1000
0035	1000	1500	1000
0036	1000	1500	1000
0037	1000	1500	1000
0038	1000	1500	1000
0039	1000	1500	1000
0040	1000	1500	1000
0041	1000	1500	1000
0042	1000	1500	1000
0043	1000	1500	1000
0044	1000	1500	1000
0045	1000	1500	1000
0046	1000	1500	1000
0047	1000	1500	1000
0048	1000	1500	1000
0049	1000	1500	1000
0050	1000	1500	1000
0051	1000	1500	1000
0052	1000	1500	1000
0053	1000	1500	1000
0054	1000	1500	1000
0055	1000	1500	1000
0056	1000	1500	1000
0057	1000	1500	1000
0058	1000	1500	1000
0059	1000	1500	1000
0060	1000	1500	1000
0061	1000	1500	1000
0062	1000	1500	1000
0063	1000	1500	1000
0064	1000	1500	1000
0065	1000	1500	1000
0066	1000	1500	1000
0067	1000	1500	1000
0068	1000	1500	1000
0069	1000	1500	1000
0070	1000	1500	1000
0071	1000	1500	1000
0072	1000	1500	1000
0073	1000	1500	1000
0074	1000	1500	1000
0075	1000	1500	1000
0076	1000	1500	1000
0077	1000	1500	1000
0078	1000	1500	1000
0079	1000	1500	1000
0080	1000	1500	1000
0081	1000	1500	1000
0082	1000	1500	1000
0083	1000	1500	1000
0084	1000	1500	1000
0085	1000	1500	1000
0086	1000	1500	1000
0087	1000	1500	1000
0088	1000	1500	1000
0089	1000	1500	1000
0090	1000		

[illegible][illegible]

00012100
40019

FLOW 0.00 270.00 780.00 1420.00 2190.00 2440.00 3120.00 3660.00 4140.00
154560.00

SURFACE AREA= 0. 250. 588. 891.

CAPACITY= 0. 2475. 3696. 11039.

ELEVATION= 1167. 1197. 1200. 1210.

CHL	SPID	COJW	LAPW	LEVL	COOL	CARIA	LAPL
1197.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

		DAM DATA		
	TOPFL	COOD	EXPD	DAMWID
	1204.5	2.9	1.5	110.

CREST LENGTH	30.	500.	950.	1400.
AT OR BELOW ELEVATION	1205.0	1210.0	1215.0	1220.0

PEAK OUTFLOW IS 3247. AT TIME 48.00 HOURS

PEAK OUTFLOW IS 3291. AT TIME 48.00 HOURS

PEAK OUTFLOW IS 4014. AT TIME 48.00 HOURS

PEAK OUTFLOW IS 5636. AT TIME 48.00 HOURS

PEAK OUTFLOW IS 16772. AT TIME 48.00 HOURS

***** ***** ***** *****

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO (ECONOMIC COMPUTATION)
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS				
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5
				.35	.40	.50	.60	1.00
HYDROGRAPH AT	1	2.49	1	16.7%	1713.	2141.	2569.	4282.
	(6.45)	(97.72)	48.50)	60.63)	72.76)	121.26)
HYDROGRAPH AT	2	1.57	1	856.	878.	1098.	1317.	2195.
	(3.95)	(24.24)	24.87)	31.08)	37.30)	62.16)
2 C. PERIOD	3	3.81	1	4525.	2590.	3238.	3885.	6475.
	(9.87)	(71.51)	73.36)	91.68)	110.02)	183.36)
FIELD TO	4	3.81	1	2500.	2565.	3206.	3848.	6429.
	(9.87)	(70.80)	72.62)	90.79)	108.95)	182.06)
HYDROGRAPH AT	5	4.56	1	2288.	2346.	2933.	3519.	5866.
	(11.81)	(64.78)	66.44)	83.05)	99.66)	166.09)
HYDROGRAPH AT	6	5.20	1	2790.	2861.	3577.	4292.	7154.
	(13.67)	(79.00)	81.03)	101.28)	121.54)	202.57)
HYDROGRAPH AT	7	1.17	1	789.	810.	1012.	1214.	2024.
	(3.03)	(22.35)	22.93)	28.66)	36.39)	57.32)
HYDROGRAPH AT	8	2.17	1	1375.	1411.	1763.	2116.	3527.
	(5.62)	(33.95)	35.25)	43.94)	53.92)	89.87)
5 COMBINED	9	16.91	1	9544.	9789.	12237.	14684.	24469.
	(43.80)	(270.27)	277.20)	346.50)	415.80)	692.90)
ROUTED TO	10	16.91	1	3247.	3291.	4014.	5636.	16772.
	(43.80)	(91.75)	93.20)	113.66)	159.58)	474.92)

D-27

PLAN 1 STATION 4
 RATIO FLOW, CFS STAGE, FT. HOURS
 11.9

.30	2500.	1204.1	44.67
.40	2565.	1204.1	44.67
.50	3206.	1204.5	44.67
.60	4868.	1204.5	44.67
1.00	6429.	1205.5	44.67

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
	OUTFLOW	1197.00	1197.00	1204.50
		2475.	2475.	6627.
		0.	0.	3255.

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.39	1204.47	0.00	6606.	3247.	0.00	48.00	0.00
.40	1204.63	.13	6724.	3291.	.33	48.00	0.00
.50	1206.22	1.72	7903.	4014.	2.17	48.00	0.00
.60	1207.62	3.12	9009.	5636.	3.17	48.00	0.00
1.00	1211.21	6.71	12139.	16772.	5.00	48.00	0.00

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 01 APR 80

1	A1	RATIOS OF PMF ROUTED THROUGH THE RESERVOIR AND DOWNSTREAM									
2	A2	DOWNSTREAM CONDITIONS DUE TO DAM BREAK TEDINBORO LAKE DAM PA-181									
3	A3	PLANS 1 & 2 ASSUMES BREACH, PLAN 3 ASSUMES NO BREACH									
4	B	288	0	10	0	0	0	0	0	-4	0
5	B1	5									
6	J	3	1	1							
7	J1	.5									
8	K	0	1								
9	K1	INFLOW SUBAREA A									
10	M	1	2.49								
11	P	23.	112	122	136	146					
12	T						1.0	0.05			
13	W	4.91	0.55								
14	X	-1.5	2.05	2.0							
15	K	0	2								
16	K1	INFLOW SUBAREA B									
17	M	1	1.32								
18	P	23.	112	122	136	146					
19	T						1.0	0.05			
20	W	9.12	0.98								
21	X	-1.5	2.0								
22	K	2	3								
23	K1	COMBINE INFLOW (SUBAREA A AND B)									
24	K	1	4								
25	K1	MOD PULS ROUTING									
26	Y										
27	Y1	1									
28	Y6	.06	.05	.06	1198	1220	5280	.0038			
29	Y7	0	1220	200	1210	896	1200	898	1198	902	1198
30	Y7	904	1200	1300	1210	1850	1220				
31	K	0	5								
32	K1	INFLOW SUBAREA C									
33	M	1	4.56								
34	P	23.	112	122	136	146					
35	T										
36	W	7.08	0.55								
37	X	-1.5	2.0								
38	K	0	6								
39	K1	INFLOW SUBAREA D									
40	M	1	5.20								
41	P	23.	112	122	136	146					
42	T										
43	W	6.53	0.55								
44	X	-1.5	2.0								
45	K	0	7								

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 01 APR 80

RUN DATE: 8/01/26.
TIME: 08.27.56.

RATIOS OF PMF ROUTED THROUGH THE RESERVOIR AND DOWNSTREAM
DOWNSTREAM CONDITIONS DUE TO DAM BREAK (EDINBORO LAKE DAM PA-18)
PLANS 1 6 2 ASSUMES BREACH, PLAN 3 ASSUMES NO BREACH

JOB SPECIFICATION
NO NHR NMIN IDAY IMR IMIN METAC IPLT IPRT NSTAN
288 0 10 0 0 0 0 -4 0
JOPER NWT LROPT TRACE
5 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 3 NRTIO= 1 LRTIO= 1

RTIOS: 230

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA A

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INHYD	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	2.49	0.00	2.49	1.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	23.00	112.00	122.00	136.00	146.00	0.00	0.00

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STNKS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 4.91 CP= .35 NTA= 0

RECESSION DATA
 STARTQ= -1.50 ORCSN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH 100 END-OF-PERIOD ORDINATES, LAG= 4.89 HOURS, CP= .55 VOL= .91									
1.	4.	9.	21.	28.	36.	44.	52.	61.	
70.	79.	89.	108.	118.	128.	137.	145.	153.	
160.	166.	171.	180.	183.	185.	187.	187.	186.	
184.	179.	174.	164.	160.	155.	151.	146.	142.	

138.	134.	130.	127.	123.	119.	116.	113.	110.	106.
103.	98.	93.	89.	85.	81.	77.	73.	69.	65.
77.	73.	69.	65.	61.	57.	53.	49.	45.	41.
58.	54.	50.	46.	42.	38.	34.	30.	26.	22.
43.	39.	35.	31.	27.	23.	19.	15.	11.	7.
32.	28.	24.	20.	16.	12.	8.	4.	0.	0.

	END-OF-PERIOD FLOW												
MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
									SUM	33.88	31.09	2.49	196267.
									(853.1)	(790.)	(63.)	3557.86

[illegible]

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA B

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTO
2	0	0	0	0	0	1	0	0

HYDROGRAPH DATA								
JUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1.33	0.00	1.32	1.00	0.000	0	1	0	

PRECIP DATA

	PM5	R5	R12	R24	R48	R72	R96
SPFE							
0-00	22.00	112.00	122.00	134.00	146.00	0.00	0.00

LOSS DATA

LOGS DATA										
LRDPT	STKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
IP= 5.12 CP= .55 NTA= 0

RECESSION DATA

UNIT HYDROGRAPHIC END-OF-PERIOD ORIGINATES, LAG=							5.13 HOURS, CP=	55	VOL=	90
STARTU=		-1.50		URCSN=		-0.05	RTIOR=		2.00	
1.	2.	4.	7.	10.	13.	17.	21.	25.	29.	
33.	38.	42.	47.	52.	57.	62.	66.	71.	74.	
78.	81.	84.	87.	89.	91.	93.	94.	95.	95.	
95.	94.	92.	89.	87.	85.	82.	80.	78.	76.	
74.	72.	68.	64.	60.	56.	52.	48.	44.	40.	
56.	54.	53.	51.	50.	49.	47.	46.	45.	43.	

END-OF-PERIOD FLOW															
0		MO.DA		HR.MN		PERIOD		RAIN		EXCS		LOSS		COMP Q	
42.	41.	40.	39.	38.	37.	36.	35.	34.	33.						
32.	31.	30.	29.	28.	27.	26.	25.	24.	23.	22.	21.	20.	19.	18.	17.
24.	23.	22.	21.	20.	19.	18.	17.	16.	15.	14.	13.	12.	11.	10.	9.
18.	17.	16.	15.	14.	13.	12.	11.	10.	9.	8.	7.	6.	5.	4.	3.
					</										

24

(853.1(790.1(63.1(2849.24)

COMBINE HYDROGRAPHS

COMBINE INFLOW (SUBAREA A AND B)

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
3	2	0	0	0	0	1	0	0

HYDROGRAPH ROUTING

MOD PULS ROUTING

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
4	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IES	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

MSIPS	MSIDL	LAG	AMSKK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	0.	0

NORMAL DEPTH CHANNEL ROUTING

QN(1)	QN(2)	QN(3)	ELNVT	ELMAX	RLNTH	SEL
.0600	.0500	.0600	1198.0	1220.0	5280.	.00380

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC

0.00	1220.00	200.00	1210.00	896.00	1200.00	898.00	1198.00	902.00	1198.00
904.00	1200.00	1300.00	1210.00	1850.00	1220.00				

STORAGE	0.00	.72	2.42	17.26	49.84	100.17	168.24	254.06	357.63
478.94	618.00	773.60	941.92	1122.34	1314.96	1519.76	1736.75	1965.93	2207.29

MAXIMUM STAGE IS 1204.5
MAXIMUM STAGE IS 1204.5

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA C

ISTAQ	IComp	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
5	0	0	0	0	0	1	0	0

IHYDG	IUNG	IAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	4.56	0.00	4.56	1.00	0.000	0	10	0

HYDROGRAPH DATA

PRECIP DATA

SPFE	PHS	R6	R12	R24	R48	R72	R96
0.00	23.00	112.00	122.00	136.00	146.00	0.00	0.00

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STNKS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 7.08 CP= .55 NTA= 0

RECESSION DATA

SIRIO= -1.50 QRCN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH100 END-OF-PERIOD ORDINATES, LAG= 7.15 HOURS, CP= .55 VOL= .79									
1.	3.	7.	11.	15.	21.	26.	32.	39.	45.
52.	59.	67.	74.	82.	90.	98.	107.	115.	123.
132.	141.	150.	158.	166.	174.	181.	188.	195.	201.
206.	211.	216.	220.	224.	228.	230.	233.	235.	236.
237.	237.	236.	235.	233.	229.	224.	220.	215.	211.
207.	203.	199.	195.	191.	187.	183.	180.	176.	173.
169.	166.	162.	159.	156.	153.	150.	147.	144.	141.
138.	136.	133.	130.	128.	125.	123.	120.	118.	115.
113.	111.	109.	106.	104.	102.	100.	98.	96.	94.
92.	91.	89.	87.	85.	84.	82.	80.	79.	77.

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	END-OF-PERIOD FLOW	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
-------	-------	--------	------	------	------	--------	--------------------	-------	-------	--------	------	------	------	--------

SUM 33.58 31.09 2.49 254756.
(853.11 790.11 63.11 7213.89)

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA D

1STAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
6 0 0 0 0 0 1 0 0

HYDROGRAPH DATA
1 IUMG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
1 5.20 0.00 5.20 1.00 0.000 0 1 0

PRECIP DATA
SPFE PHS R6 R12 R24 R48 R72 R96
0.00 23.00 112.00 122.00 136.00 146.00 0.00 0.00

LOSS DATA
LROPT STRKR DLTKR RTIOL ERAIN STAKS RTIOK STRTL CNSTL ALSMX RTIMP
0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 1.00 0.00 0.00 0.00

UNIT HYDROGRAPH DATA
TP= 6.53 CP= .55 NTA= 0

RECESSION DATA
STRTO= -1.50 QRCSEN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH100 END-OF-PERIOD ORDINATES, LAG= 6.56 HOURS, CP= .55 VOL= .82

1.	4.	9.	15.	22.	29.	37.	45.	54.	64.
73.	83.	94.	105.	115.	126.	137.	149.	161.	172.
184.	196.	207.	217.	227.	236.	245.	252.	260.	266.
272.	277.	282.	286.	289.	291.	293.	293.	293.	292.
289.	284.	278.	272.	266.	260.	255.	249.	244.	239.
233.	228.	223.	219.	214.	209.	205.	200.	196.	192.
188.	184.	180.	176.	172.	168.	165.	161.	158.	154.
151.	148.	145.	141.	138.	135.	132.	130.	127.	124.
121.	119.	116.	114.	111.	109.	107.	104.	102.	100.
98.	96.	94.	91.	90.	88.	86.	84.	82.	80.

0 MO.DA HR.MN PERIOD RAIN EXCS LOSS END-OF-PERIOD FLOW
MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q

SUM 33.58 31.09 2.49 318598.
1 853.11 790.11 63.11 9021.69

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA E

1STAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO

LROPT STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .05 0.00 0.00

UNIT HYDROGRAPH DATA

IP= 4.87 CP= .55 NTA= 0

STRIQ= -1.50 ORCSN= -.05 RTIOR= 2.00
 RECESION DATA

UNIT HYDROGRAPH 100 END-OF-PERIOD ORDINATES, LAG= 4.87 HOURS, CP= .55 VOL= .91
 1. 2. 4. 7. 10. 13. 17. 21. 25. 29.
 33. 38. 42. 47. 52. 56. 61. 65. 69. 73.
 76. 79. 81. 84. 85. 87. 88. 89. 89. 88.
 87. 85. 82. 80. 77. 75. 73. 71. 69. 67.
 65. 63. 61. 59. 56. 54. 52. 51. 50. 49.
 48. 47. 46. 44. 43. 42. 41. 39. 38. 37.
 36. 35. 34. 33. 32. 31. 30. 29. 29. 28.
 27. 26. 25. 24. 23. 23. 22. 21. 21. 21.
 20. 20. 19. 18. 17. 17. 16. 16. 15. 15.
 15. 15. 14. 14. 13. 13. 13. 12. 12. 12.

END-OF-PERIOD FLOW

MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q
 0
 SUM 33.58 31.09 2.49 92746.
 1853:11 190:11 63:11 2626:271

***** ***** ***** ***** *****

SUB-AREA RUNOFF COMPUTATION

INFLOW SUBAREA F

ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
 8 0 0 0 0 0 1 0 0

IHYDG IUNG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
 1 1 2.17 0.00 2.17 1.00 0.000 0 1 0

PRECIP DATA

SPFE PMS R6 R12 R24 R48 R72 R96
 0.00 23.00 112.00 122.00 136.00 146.00 0.00 0.00

LROPT STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 LOSS DATA

0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 0.05 0.00 0.00

UNIT HYDROGRAPH DATA

TP= 5.28 CP= .55 RTA= 0

RECESSION DATA

STRTD= -1.50 ORCSN= -.005 RTIOR= 2.00

1. UNIT HYDROGRAPH100 END-OF-PERIOD ORDINATES, LAG= 9.27 HOURS, CP= .29 VOL= .89
 3. 7. 11. 15. 20. 26. 32. 38. 44.

O	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP O	END-OF-PERIOD FLOW	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP O	
												SUM	33.58	31.09	2.49	161249.
													790.11	63.11	4574.53	

100

COMBINE HYDROGRAPHS

CONTAINING INFLOW (SUBAREAS A,B,C,D,E AND F)

ISTAQ	ICOMP	IECON	ITYPE	JPLT	JPRI	INAME	ISTAGE	IAUDIO
9	5	0	0	0	0	1	0	0

.....

HYDROGRAPH ROUTING

ROUTE THRU EDINBORO LAKE

TSIAG	ICOMP	TECON	ITAPE	JPLY	JPRY	INAME	TSTAGE	TAUTO
10	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	LOPT	IPMP	LSTR
QLOSS	CLOSS	AVG	IRES	ISAME	LOPT	IPMP	LSTR

DATE	DESCRIPTION	AMOUNT	BALANCE
1960-1-1	Initial deposit	100.00	100.00
1960-1-15	Withdrawal	25.00	75.00
1960-2-1	Deposit	50.00	125.00
1960-2-15	Withdrawal	10.00	115.00
1960-3-1	Deposit	75.00	190.00
1960-3-15	Withdrawal	30.00	160.00
1960-4-1	Deposit	40.00	200.00
1960-4-15	Withdrawal	15.00	185.00
1960-5-1	Deposit	60.00	245.00
1960-5-15	Withdrawal	20.00	225.00
1960-6-1	Deposit	80.00	305.00
1960-6-15	Withdrawal	35.00	270.00
1960-7-1	Deposit	55.00	325.00
1960-7-15	Withdrawal	25.00	300.00
1960-8-1	Deposit	70.00	370.00
1960-8-15	Withdrawal	30.00	340.00
1960-9-1	Deposit	45.00	385.00
1960-9-15	Withdrawal	18.00	367.00
1960-10-1	Deposit	65.00	432.00
1960-10-15	Withdrawal	22.00	410.00
1960-11-1	Deposit	50.00	460.00
1960-11-15	Withdrawal	28.00	432.00
1960-12-1	Deposit	70.00	502.00
1960-12-15	Withdrawal	32.00	470.00
1961-1-1	Deposit	40.00	510.00
1961-1-15	Withdrawal	15.00	495.00
1961-2-1	Deposit	60.00	555.00
1961-2-15	Withdrawal	25.00	530.00
1961-3-1	Deposit	85.00	615.00
1961-3-15	Withdrawal	38.00	577.00
1961-4-1	Deposit	50.00	627.00
1961-4-15	Withdrawal	20.00	607.00
1961-5-1	Deposit	75.00	682.00
1961-5-15	Withdrawal	30.00	652.00
1961-6-1	Deposit	45.00	697.00
1961-6-15	Withdrawal	18.00	679.00
1961-7-1	Deposit	65.00	744.00
1961-7-15	Withdrawal	22.00	722.00
1961-8-1	Deposit	55.00	777.00
1961-8-15	Withdrawal	28.00	749.00
1961-9-1	Deposit	70.00	819.00
1961-9-15	Withdrawal	32.00	787.00
1961-10-1	Deposit	40.00	827.00
1961-10-15	Withdrawal	15.00	812.00
1961-11-1	Deposit	60.00	872.00
1961-11-15	Withdrawal	25.00	847.00
1961-12-1	Deposit	85.00	932.00
1961-12-15	Withdrawal	38.00	894.00
1962-1-1	Deposit	50.00	944.00
1962-1-15	Withdrawal	20.00	924.00
1962-2-1	Deposit	75.00	999.00
1962-2-15	Withdrawal	30.00	969.00
1962-3-1	Deposit	45.00	1014.00
1962-3-15	Withdrawal	18.00	996.00
1962-4-1	Deposit	65.00	1061.00
1962-4-15	Withdrawal	22.00	1039.00
1962-5-1	Deposit	55.00	1094.00
1962-5-15	Withdrawal	28.00	1066.00
1962-6-1	Deposit	70.00	1136.00
1962-6-15	Withdrawal	32.00	1104.00
1962-7-1	Deposit	40.00	1144.00
1962-7-15	Withdrawal	15.00	1129.00
1962-8-1	Deposit	60.00	1189.00
1962-8-15	Withdrawal	25.00	1164.00
1962-9-1	Deposit	85.00	1249.00
1962-9-15	Withdrawal	38.00	1211.00
1962-10-1	Deposit	50.00	1261.00
1962-10-15	Withdrawal	20.00	1241.00
1962-11-1	Deposit	75.00	1316.00
1962-11-15	Withdrawal	30.00	1286.00
1962-12-1	Deposit	45.00	1331.00
1962-12-15	Withdrawal	18.00	1313.00
1963-1-1	Deposit	65.00	1378.00
1963-1-15	Withdrawal	22.00	1356.00
1963-2-1	Deposit	55.00	1411.00
1963-2-15	Withdrawal	28.00	1383.00
1963-3-1	Deposit	70.00	1453.00

[illegible]

NSIPS	NSTDL	LAG	AMSKK	X	YSK	STURA	ISPRAT
						-1187-	-1

Account	1967	1968	1969	1970	1971
11417- 000.0	000.0	000.0	0	0	1

[illegible]

FLOW	0.00	270.00	780.00	1420.00	2190.00	2440.00	3120.00	3660.00	4140.00
154560.00									
SURFACE AREA=	0.	250.	588.	891.					
CAPACITY=	0.	2475.	3696.	11039.					
ELEVATION=	1167.	1197.	1200.	1210.					
		CREL	SPWID	COQW	EXPW	ELEVL	COOL	CAREA	EXPL
		1197.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

1 0 0 0.000 0.000 0.000 0

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELNVT	ELMAX	RLNTH	SEL
.0600	.0500	.0600	1186.0	1200.0	1000.	.30100

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

0.00 1200.00 90.00 1190.00 100.00 1187.00 105.00 1186.00 135.00 1186.00
 140.00 1190.00 150.00 1190.00 225.00 1200.00

STORAGE 0.00 .95 1.17 1.84 2.58 3.37 4.34 5.58 7.02
 1218.67 10.32 12.58 14.84 17.31 19.98 22.87 25.95 29.24 32.74
 1236.44

OUTFLOW 0.00 17.37 38.06 118.55 196.87 292.49 409.30 556.74 735.44
 154947.74 1196.16 1482.21 1811.30 2182.79 2599.96 3065.05 3580.24 4147.64 4769.34
 155447.39

STAGE 1186.00 1186.74 1187.47 1188.21 1188.95 1189.68 1190.42 1191.16 1191.89
 1192.63 1193.37 1194.11 1194.84 1195.58 1196.32 1197.05 1197.79 1198.53 1199.26
 1200.00

FLOW 0.00 17.37 58.06 118.55 196.87 292.49 409.30 556.74 735.44
 155947.74 1196.16 1482.21 1811.30 2182.79 2599.96 3065.05 3580.24 4147.64 4769.34
 155447.39

MAXIMUM STAGE IS 1198.3

MAXIMUM STAGE IS 1209.6

MAXIMUM STAGE IS 1198.3

***** ***** ***** *****

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION STATION AREA PLAN RATIO 1
 .50

HYDROGRAPH AT 1 2.49 1 2141.
 (6.45) (60.63)
 2 2141.
 (60.63)
 3 2141.
 (60.63)

HYDROGRAPH AT 2 1.32 1 1098.
 (3.42) (31.08)
 2 1098.
 (31.08)
 3 1098.
 (31.08)

2 COMBINED 3 3.81 1 3238.
 (9.87) (91.68)
 2 3238.
 (91.68)
 3 3238.
 (91.68)

ROUTED TO 4 3.81 1 3206.
 (9.87) (90.79)
 2 3206.
 (90.79)
 3 3206.
 (90.79)

HYDROGRAPH AT 5 4.56 1 2933.
 (11.81) (83.05)
 2 2933.
 (83.05)
 3 2933.
 (83.05)

HYDROGRAPH AT 6 5.20 1 3577.
 (13.47) (101.28)

2	3577.		
(101.28)		
3	3577.		
(101.28)		
HYDROGRAPH AT	7	1.17	1012.
	(3.03)	28.66)
			1012.
			28.66)
			1012.

AD-A097 237

KIMBALL (L ROBERT) AND ASSOCIATES EBENSBURG PA
NATIONAL DAM INSPECTION PROGRAM. OHIO RIVER BASIN, CONNEAUTEE C--ETC(U)
MAR 81

F/G 13/13
DACW31-81-C-0012
NL

UNCLASSIFIED

2 of 2

481-A
89-247

END
DATE
FILMED
5-81
DTIC

HYDROGRAPH AT	8	2.17 5.62	1 2 3	1763. 49.93 1763. 49.93 1763. 49.93	28.66
S COMBINED	9	16.91 43.80	1 2 3	12237. 346.50 12237. 346.50 12237. 346.50	
ROUTED TO	10	16.91 43.80	1 2 3	4037. 114.32 22530. 637.97 4016. 113.66	
ROUTED TO	10	16.91 43.80	1 2 3	3993. 113.07 14296. 404.77 3981. 112.72	

D-51

PLAN 1		STATION 4	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.50	3206.	1204.5	44.67
PLAN 2		STATION 4	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.50	3206.	1204.5	44.67
PLAN 3		STATION 4	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.50	3206.	1204.5	44.67

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	1197.00	1197.00	1204.50
W.S.ELEV	2475.	2475.	6627.
OUTFLOW	0.	0.	3255.

RATIO

OF

PMF

RATIO OF PMF	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.50	1.72	7903.	4037.	2.17	48.00	47.83

PLAN 2

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	1197.00	1197.00	1204.50
W.S.ELEV	2475.	2475.	6627.
OUTFLOW	0.	0.	3255.

RATIO

OF

PMF

RATIO OF PMF	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.50	1.66	7856.	22530.	2.17	48.00	47.83

PLAN 3

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	1197.00	1197.00	1204.50
W.S.ELEV	2475.	2475.	6627.
OUTFLOW	0.	0.	3255.

RATIO

OF

PMF

RATIO OF PMF	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.50	1.72	7903.	4014.	2.17	48.00	0.00


PLAN 1 STATION 10


RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.50	3993.	1198.3	48.00

13/43

PLAN 2		STATION 10	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.50	14294.	1209.6	48.00
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.50	3861.	1186.3	48.00



APPENDIX E
DRAWINGS





EDINBORO LAKE DAM

DRAINAGE AREA MAP
SCALE: 1" = 5000'




**SITE LOCATION MAP
ERIE COUNTY, PENNSYLVANIA**

APPENDIX F
GEOLOGY

General Geology

The Edinboro Lake Dam is located in the Glaciated Section of the Appalachian Plateaus Province. This section is an area where the advancing and retreating ice sheets of pleistocene time deposited drift over the bedrock and filled the valleys with glacial outwash. This drift and glacial outwash is generally composed of clay, sand, and gravel, though in some places the drift is a dense impervious till. The sand and gravel of the glacial drift are by far the largest producers of groundwater in this area. The bedrock underlying the dam consists of gray and brown shale and sandstone, with some limestone, belonging to the Catteraugus Formation of Upper Devonian Age. The rocks generally appear to be horizontal, though there is a slight regional dip to the south of less than one degree. Irregularities in the dip do exist, but are usually slight. No faulting is indicated in the vicinity of the Edinboro Lake Dam.



GEOLOGIC MAP OF AREA AROUND EDINBORO LAKE DAM

SCALE 1:250,000

QUATERNARY
PLEISTOCENE

NORTHWESTERN PENNSYLVANIA

EASTERN PENNSYLVANIA

- Border of Ashtabula drift
- - - Border of Hiram drift
- · · Border of Lavery drift
- · · Border of Kent drift

Cary Substage
Wisconsin Stage

- · · Border of Wisconsin drift

Cape May Formation
Sands and gravels with clay and silt in the base locally includes areas of Recent alluvium and swamp deposits

DEVONIAN

WESTERN PENNSYLVANIA

Dot Dr Osgway Formation
In Ashtabula and other areas, this formation is considered equivalent to the Osgway Formation of the Erie and Huron Counties, but is probably not comparable with the Osgway Formation of the Erie and Huron Counties.

Dcr Cattaraugus Formation
This formation is composed of alternating layers of sandstone and shale, and is considered equivalent to the Cattaraugus Formation of the Erie and Huron Counties, but is probably not comparable with the Cattaraugus Formation of the Erie and Huron Counties.

Dct Conneaut Group
Alternating gray, brown, greenish and purple shales and siltstones, includes "pink rock" at diller and "Channing" and "Crawford" Formations of northwest Pennsylvania.

Dco Canadaaway Formation
Alternating brown shales and sandstones, includes "Pottsville" Formation of northwestern Pennsylvania.


APPENDIX G
STABILITY ANALYSIS



NUMBER _____

BY DATE

Stability Analysis



Assumptions: 1. Velocity head is negligible
length of spillway = 83'

$$A = (83)(7) = 581 \text{ kg}$$

From HEC 1 result, $Q = 4000 \text{ cfs}$ $y = \frac{4000}{581} = 6.88 \text{ --}$



L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EDENSBURG PENNSYLVANIA

NAME _____

NUMBER _____

SHEET NO. 2 OF 5

BY TS DATE _____

$$P_v = \frac{V^2}{2g} = 0.74 \text{ ft} \quad \therefore \text{neglected}$$


2. Assume tailwater elevation is at 11.192'

From Manning's Formula

$$Q = \frac{1.49}{n} A R^{2/3} S^{1/2}, \quad Q = \text{down cfs}, S = 0.001$$

(From HEC 1)

Assuming downstream channel is rectangular-shaped



$$n = 0.035$$

$$Q = \frac{1.49}{0.035} (150d) \left[\frac{150d}{150+2d} \right]^{2/3} (0.001)^{1/2} \quad \therefore d = 6'$$

$$\text{Elevation}_{\text{tailwater}} = 11.88 + 6 = 11.94'$$

3. γ_s for silt and gravel = 2.65
4. ϕ for silt and gravel = 30°
5. dry unit weight of silt & gravel = 100 pcf
6. unit weight of rubble concrete = 145 pcf
7. coeff. of friction between concrete and gravel = 0.50
7. uplift pressure is linearly distributed.



L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____

NUMBER _____

SHEET NO. 3 OF 5BY TS DATE _____

Water Pressure

$$P_1 = (3)(62.4)(11) = 2059.2 \text{ \#}$$

$$P_2 = \frac{(11)^2}{2}(62.4) = 3775.2 \text{ \#}$$

$$P_5 = (2)(9)\left(\frac{1}{2}\right)(62.4) = 561.60 \text{ \#}$$

$$P_6 = (3)(6)(62.4) = 1123.2 \text{ \#}$$

$$P_7 = (10)^2\left(\frac{1}{2}\right)(62.4) = 3120.0 \text{ \#}$$

Effective Earth Pressure

Submerged Unit weight of soil = γ_{sat}

$$= 100 \left(\frac{2.65 - 1}{2.65} \right) = 62.26 \text{ pcf}$$

$$P_3 = \frac{(62.26)(7)^2}{2} \left(\frac{1 - \sin 30}{1 + \sin 30} \right) = 508.46 \text{ \#}$$

$$P_4 = (1.11)(5)\left(\frac{1}{2}\right)(62.26) = 172.11 \text{ \#}$$

$$P_8 = \frac{(4)^2}{2}(62.26) \left(\frac{1 + \sin 30}{1 - \sin 30} \right) = 1494.20 \text{ \#}$$

Weight of the Dam

$$W_1 = (2)(1)(145) = 290 \text{ lb}$$

$$W_2 = (4)(2)(145) = 1160 \text{ lb}$$

$$W_3 = \frac{1}{2}(4.25)(9)(145) = 2773.13 \text{ lb}$$

$$W_4 = (2)(6)(145) = 1740.0 \text{ lb}$$

$$W_5 = (6.75)(9)(145) = 978.75 \text{ lb}$$



L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____

NUMBER _____

SHEET NO. 4 OF 5

BY JS DATE _____

$$W_6 = (2)(9)(\frac{1}{2})(145) = 1305 \#$$

$$\text{Total wt: } 8246.88 \#$$

Lift Water Pressure

$$W_{u1} = (7)(62.4)(10) = 4368 \#$$

$$W_{u2} = (\frac{1}{2})(7)(62.4)(10) = 2184 \#$$

$$\frac{1}{2} W_{u2} = 6552 \#$$

Stability Against Sliding

$$F.S. = \frac{(8246.88 - 6552 + 172.77 + 561.60 + 1123.21 + 3120 + 1624.24)}{2059.2 + 3775.2 + 508.46}$$

Sliding

$$= \frac{6390.47}{6342.86} = 1.01 < 1.5$$

Stability against overturning (Neglect F_2)

$$\text{Resisting Moment} = (290)(1) + (1160)(3) + (2775.13)(5 + \frac{214.25}{3})$$

$$+ (1740)(7) + (978.75)(7.25 + \frac{0.75}{2}) + (1305)(8 + \frac{2}{3})$$

$$+ (172.77)(10 - \frac{1.11}{3}) + (561.60)(10 - \frac{2}{3}) + (1123.21)(11.5)$$

$$+ (3120)(7 - \frac{2}{3})$$

$$= 290 + 3480 + 16176.59 + 12180 + 7462.97 + 11310.22$$

$$+ 1663.78 + 5241.41 + 1684.8 + 1040$$

$$= 60529.99 \text{ ft-lb}$$

Driving Moment

$$= (2059.2)(5.5 - 1) + (3775.2)(\frac{11}{3} - 1) + (508.46)(\frac{7}{3} - 1) + (2184)(1.5)$$

$$(15) + 2184(\frac{2}{3}) = 9266.4 + 10067.2 + 577.95 + 21840 + 14560$$

$$= 56411.55 \text{ ft-lb}$$



L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____

NUMBER _____

SHEET NO. 5 OF 5

BY JS DATE _____

$$F.S. \text{ overturning} = 1.07 < 1.5$$

$$\Sigma V = 8246. + 172.77 + 561.60 + 1123.2 - 6552 = 3551.57 \text{ lb}$$

$$\Sigma M = 60529.99 - 56411.55 = 4118.44 \text{ ft-lb}$$

$$\frac{\Sigma M}{\Sigma V} = 1.16 \text{ ft}$$

$\frac{1}{3}(11) = 3.67' > 1.16'$: resultant falls
outside of the middle third of the
base.

DATE
ILMED
-8